



3-D VIEW

TOTAL TONNAGE IN KILOS	MEMBERS		CLEATS		PLATES		BOLTS
	QTY	KILOS	QTY	KILOS	QTY	KILOS	QTY
106401	1538	80062	193	120	4490	26219	4928

REV	REVISION DESCRIPTION	DATE
A	ISSUED FOR APPROVAL	08/05/02
B	ISSUED FOR CONSTRUCTION	13/06/02

GENERAL NOTES

- ALL DIMENSIONS ARE IN MILLIMETRES U.N.O.
- ALL PLATES TO BE TO AS 3678 GR 250 U.N.O.
- ALL SECTIONS TO BE AS 3679 GR 300+ U.N.O.
- ALL RHS AND SHS TO BE TO AS 1163 GR 350 U.N.O.
- ALL NOTCHES IN MEMBER TO HAVE 11mm RADIUS IN CORNER
- MARK Nos. MUST BE CLEARLY SHOWN ON ALL ITEMS
- WELDING SYMBOLS SHOWN ARE TO AS Z6
- ALL WELDS 6 mm CONT. FILLET U.N.O.
- ALL WELDING AND WELD PREPARATION FOR STRUCTURAL MEMBERS TO BE AS 1534, Part 1
- GRIND SMOOTH ALL SHARP CORNERS
- ALL HOLES 22 DIA U.N.O.

CLIENT: **ALLMEN INDUSTRIES PTY LTD**
 PROJECT: **ZONE-E (SITE-2) KING ST. WHARF**
 TITLE: **SHADE STRUCTURE & AWNING STEELWORK DETAILS**

BY	DATE	REV
BP	13/06/02	B
NAM	13/06/02	
NTS	SHEET SIZE A1	

Ph: 9629 4976 Fax: 9629 4975
 DRAWING No: **U-AEV4**
 JOB No: **1247AL**